1999 AP -8 PM 3: 47 FOLLOW UP

INDEXED PROOFED_

T. HO. 99- 1059 SE MEEVES. RECORDER Deneu Mewer

UNITED STATES PUBLIC LAND SURVEY CORNER CERTIFICATE

LAND SURVEY MONUMENTS SITUATED IN SECTION 9 .. TOWNSHIP 85 NORTH, RANGE 41 WEST, OF THE 5th PRINCIPAL MERIDIAN, CRAWFORD COUNTY, IOWA.

PREVIOUSLY RECORDED IN BOOK: _____,PAGE: _ MONUMENT DESCRIPTION AND REMARKS: .


1). NW Corner 9-85-41; Set 5/8" Rebar w/ Cap No. 14052, 4" Deep


2). N 1/4 Corner 9-85-41; Fd Conc. Monu., 3.5' Deep, Set 5/8" Rebar w Cap No. 14052 atop

Stone ties were obtained from Crawford County Engineer's Office, were field verified and retied.

PLAN-VIEW

NW Corner 9-85-41 Set 5/8" Rebar w/ Cap No. 14052, 4" Deep







N 1/4 Corner 9-85-41 Fd Conc. Monu., 3.5' Deep, Set 5/8" Rebar w Cap No. 14052 atop.

NW Corner

Fd nothing at tie location. Set 5/8" Rebar w/ Cap No. 14052 with use of ties. Fit both Centerlines well and was in line eith fence line to the North.





I hereby certify that this land surveying document was prepared and the related survey work was performed by me or under my direct personal supervision and that I am a duly licensed Land Surveyor under the laws of the State of lower

Nd Surveyor

14052

My registration renewal date is December 31, 2000 Pages or sheets covered by this seal: _ONE

Corners to be indexed Twp. Range Corner NW Cor. 85 N 1/4 Cor. 85 41

4/01/99

Date

L and H Engineers & Surveyors

117 South 2nd Street Cherokee, lowa 51012 Tel. (712) 225-0560 Fax (712) 225-8017